



American Samoa Power Authority

P.O. Box PPB
Pago Pago, American Samoa 96799
Telephone: (684) 699-3057
Email: procurement@aspower.com
Website: www.aspower.com



REQUEST FOR QUOTATIONS

SUPPLY & DELIVERY OF WAREHOUSE BUILDING MATERIALS

(PVC Pipes & Distribution Transformer Storage Sheds)

RFQ NO. ASPA24.011

Issuance Date: NOVEMBER 27, 2023

Closing Date/Time: DECEMBER 07, 2023

|

APPROVED FOR ISSUANCE BY:

**WALLON YOUNG F.
ASPA Executive Director**

TAFUNA WAREHOUSE STORAGE SHEDS

No.	MATERIAL	FINISH	LENGTH	QUANTITY
1	Universal Columns - 200UC 46	Hot Dipped Galvanized (HDG)	6.0M	30
2	Universal Beams 200 UB 25	Hot Dipped Galvanized (HDG)	7M	24
3	Universal Beams 200 UB 25	Hot Dipped Galvanized (HDG)	6M	20
4	Flats - 150mm x 16mm	Hot Dipped Galvanized (HDG)	6M	4
5	Flats - 200mm x 16mm	Hot Dipped Galvanized (HDG)	6M	4
6	Flats - 200mm x 20 mm	Hot Dipped Galvanized (HDG)	6M	4
7	Flats - 250mm x 20mm	Hot Dipped Galvanized (HDG)	6M	4
8	Purlins HST200 /18 Profile -III Span - 7M Braces 2	Hot Dipped Galvanized (HDG)	7M	100
9	Braces - Adjustable bolted (for HST200 /18 Purlins)	Hot Dipped Galvanized (HDG)	1.2M	160
10	Cleats- Internal support	Hot Dipped Galvanized (HDG)	150mm	87
11	Cleats - End Support	Hot Dipped Galvanized (HDG)	80mm	32
12	Galvanized Assemblies (Bolt / Nut/ Washer Set)	Hot Dipped Galvanized (HDG)	M16 X 80mm	280
13	Galvanized Assemblies (Bolt / Nut/ Washer Set)	Hot Dipped Galvanized (HDG)	M20 X 70mm	280
14	Purlin Flange Assemblies (Bolt/ Nut/ Washer Set)	Hot Dipped Galvanized (HDG)	M20 X 30mm	400